WEST GLENDOWER PLACE
S-90-2007



Zoning:	**R-4**	Acres:	**2.83**
Planning District:	**Northwest**	Number of Lots:	**7**
CAC:	**Northwest**	Planner:	**Jacque Baker**
Drainage Basin:	**Hare Snipe Creek**	Phone:	**(919) 516-2630**
		Applicant Contact:	**Thompson & Associates**
		Phone:	**(919) 577-0808**


TYPICAL ROADWAY SECTION – PLEASANT GROVE CH. RD.
60' RIGHT OF WAY W/ 41' B-B
NTS
SECONDARY TREE CONSERVATION AREA
65' WIDE PERIMETER YARD
SEGMENTS PG 01-PG-04
12,351 SF = 0.284 AC
ALTERNATE COMPLIANCE SECONDARY
TREE CONSERVATION AREA
65' WIDE PERIMETER YARD
SEGMENTS PG 05-PG-08
11,696 SF = 0.269 AC
0.552 ac
TREE CONSERVATION
AREA
BOM 1986-46
LAYTON GLEN SUBDIVISION
BOM 1976-448
PICKWICK VILLAGE SUBDIVISION
GLENDOWER RD.
OLD COLONY RD.
PRINTER LANE
HAMMERSMITH DR
WOODEN SHOE LN.
BOM 1979-878
HOLLAND PARK SUBDIVISION
PLEASANT GROVE CHURCH RD. 60' PUBLIC R/W
EX. HOUSE
EX. HOUSES TO BE REMOVED
IMPROVE PLEASANT GROVE CHURCH RD. TO 1/2 41' B/B SECTION WITH 5' CONC. SIDEWALK PROJECT SIDE.
ALL STREETS SHOWN ON THESE PLANS SHALL HAVE A FULL WIDTH OF THE RIGHT-OF-WAY CLEARED AND GRADED WITHIN 50 FEET OF ALL STREET INTERSECTIONS.
VICINITY MAP
NTS
SITE
LEESVILLE RD
LAWN RD
CLEARBROOK RD
OLD COLONY RD
HAMMERSMITH DR
CLEARBROOK DR
HALLMARK DR
PLEASANT GROVE CHURCH RD
KENSWICK AVE
WEST MILLBROOK RD
SMALL SUBDIVISION NOTES:
TOTAL AREA OF PROPOSED SUBDIVISION = 2.83 ACRES
AREA LESS THAN 5 ACRES THEREFORE CONDITION MET
PROPERTY IS ZONED RESIDENTIAL R-4
RESIDENTIAL ZONING THEREFORE CONDITION MET
PERCENTAGE OF PERIPHERY OF THE PROPOSED SUBDIVISION ABUTTING EXISTING RESIDENTIAL BUILDING LOTS CONTAINING SINGLE FAMILY DETACHED DWELLINGS IS 100%
100% GRATER THAN 66% THEREFORE CONDITION MET
THE PROPOSED SUBDIVISION CONTAINS ANY LOT WHICH IS 80% OR LESS THAN THE MEDIAN LOT SIZE OF THE SURROUNDING PERIPHERY DEVELOPED RESIDENTIAL LOTS
THE MEDIAN SURROUNDING RESIDENTIAL LOT SIZE = 15,594 SF
SMALLEST PROPOSED LOT = 10,890 SF
80% OF 15,594 SF = 12,475.2 SF (GREATER THAN 10,890 SF) THEREFORE CONDITION IS MET
BASED UPON SECTION 10-3033 UNDER DEFINITION OF INFILL. ALL FOUR CONDITIONS ARE MET. THEREFORE PROJECT IS AN INFILL
SITE DATA
PIN = 0787-61-1247, 0787-61-2036
ZONING = R-4
TOTAL TRACT SIZE = 2.83 ACRES
TREE CONSERVATION AREA 0.552 AC
AREA IN LOTS = 2.276 ACRES
NUMBER OF LOTS = 7
MINIMUM LOT SIZE = 10,890 SF
AVERAGE LOT SIZE = 14,175.7 SF
BOUNDARY TAKEN FROM SURVEY BY THIS OFFICE.
TOPO TAKEN FROM WAKE COUNTY GIS.
CONTOUR INTERVAL IS 2'.
LENGTH OF WATER LINE = N/A (EXISTING)
LENGTH OF SANITARY SEWER = 537 L.F. (8" PVC)
LENGTH OF NEW STREET = N/A (EXISTING)
LENGTH OF NEW SIDEWALK (PLEASANT GROVE CH. RD) = 160 L.F.
NOTE:
ALL INTERSECTION R/W RADII ARE 25.00' (PROPERTY LINES)
ALL INTERSECTION BACK OF CURB RADII ARE 30.00' (TRAVEL LANE)
NOTE:
WORK AND IMPROVEMENTS SHALL BE AS PER CITY OF RALEIGH AND N.C. DOT STANDARDS AND SPECIFICATIONS.
NOTE:
THE MINIMUM CORNER CLEARANCE FROM THE CURB LINE OF INTERSECTING STREETS SHALL BE AT LEAST 20' FROM POINT OF TANGENCY. THE RADIUS OF THE DRIVEWAY SHALL NOT ENCROACH ON THE MINIMUM CORNER CLEARANCE.
STREET TREE NOTES:
TREES REQUIRED = 1777' ROAD FRONTAGE/50 = 36 2" CAL. TREES
STREETSCAPE BUFFER PLANT LIST
TREES
SYMBOL | QUA. | BOTANICAL NAME | COMMON NAME | HEIGHT | SIZE
11 | ACER RUBRUM | RED MAPLE | 10'-12' | 2" CAL. (MIN) | 50' O.C. (MAX)
OWNER/DEVELOPER:
LAWRENCE HOMES
1129 FOOTHILLS TRAIL
WAKE FOREST, NC 27587
(919) 528-7767
SHEET 1
PRELIMINARY SITE PLAN
WEST GLENDOWER PLACE
LEESVILLE TOWNSHIP WAKE COUNTY NORTH CAROLINA
OWNER: LAWRENCE HOMES ZONED R-4
DATE 10-31-07 DRAWN WTH JOB NO.
SCALE 1" = 50' SURVEYED REM DWG GLENDOW-SITE
REVISIONS PIN = 0787-61-1247, 0787-61-2036