THE OASIS
S-4-2015



Zoning:	**R-10 CU, SHOD-3**
CAC:	**Northeast**
Drainage Basin:	**Beaver**
Acreage:	**11.56**
Number of Lots:	**36**

Planner:	**Michael Walters**
Phone:	**(919) 996-2636**
Applicant:	**Yathrib Oasis**
Phone:	**(919) 537-2499**

Planning & Development

Development Services
Customer Service Center
One Exchange Plaza
1 Exchange Plaza, Suite 400
Raleigh, North Carolina 27601
Phone 919-996-2495
Fax 919-516-2685

5-4-2015

Preliminary Development Plan Application

When submitting plans, please check appropriate review type and include the Plan Checklist document.

Preliminary Approvals		FOR OFFICE USE ONLY
☐ Site Plans for Planning Commission ☐ Preliminary Administrative Site Plans ☐ Group Housing ** ☐ Multifamily (Infill)**	■ Subdivision* ☐ Cluster Subdivision** ☐ Infill Subdivision** ☐ Expedited Subdivision Review ☐ Conventional Subdivision ☐ Compact Development ☐ Conservation Subdivision	Transaction Number 422364 Assigned Project Coordinator Nawsome Assigned Team Leader walters 1
* May require Planning Commission or City Council Approval	** Legacy Districts Only	

Has your project previously been through the Due Diligence process? If yes, provide the transaction #

GENERAL INFORMATION

Development Name : The Oasis

Proposed Use : Single Family Residential

Property Address(es) : 5520 Louisburg Road

Wake County Property Identification Number(s) for each parcel to which these guidelines will apply:

P.I.N. Recorded Deed	P.I.N. Recorded Deed	P.I.N. Recorded Deed	P.I.N. Recorded Deed
1736-15-0379			

What is your project type? ☐ Apartment ☐ Banks ☐ Elderly Facilities ☐ Hospitals ☐ Hotels/Motels ☐ Industrial Building ☐ Mixed Residential ☐ Non-Residential Condo ☐ Office ☐ Religious Institutions ☐ Residential Condo ☐ Retail ☐ School ☐ Shopping Center ■ Single Family ☐ Telecommunication Tower ☐ Townhouse ☐ Other: If other, please describe:

PRELIMINARY ADMINISTRATIVE REVIEW	Per City Code Section 10-2132.2, summarize the reason(s) this plan can be reviewed administratively not requiring Planning Commission or City Council approval. The plan does not fall under the categories listed in Article 10.2.3.a. Table in 10.1.8
PLANNING COMMISSION	Per City Code Section 10-2132.2, summarize the reason(s) this plan requires Planning Commission or City Council Preliminary Approval.
CLIENT (Owner or Developer)	Company : MYCC; Art Builders, LLC; Yathrib Oasis, LLC — Name (s) : Khalid Baloch, Waleed Elhentaty, Ashraf El Fadaly Address : 114 Rocklyn Lane Apex, NC 27502 Phone : 919-537-2499 — Email : yathrib@fadalygroup.com — Fax : N/A
CONSULTANT (Contact Person for Plans)	Company : SEPI Engineering & Construction, Inc. — Name (s) : Mitch Craig, PE Address : 1025 Wade Avenue Raleigh, NC 27605 Phone : 919-573-9937 — Email MCraig@sepiengineering.com — Fax 919.789.9591

Zoning Information	Building Information
Zoning District(s): R10	Proposed building use(s) Single Family,
If more than one district, provide the acreage of each	Existing Building(s) sq. ft. gross: N/A
Overlay District: SHOD-3	Proposed Building(s) sq. ft. gross N/A
Total Site Acres 11.56 Inside City Limits ☐ Yes ■ No	Total sq. ft. gross (existing & proposed) N/A
Off street parking Required: N/A Provided: N/A	Proposed height of building(s) N/A
COA (Certificate of Appropriateness) case #: N/A	FAR (floor area ratio percentage) N/A
BOA (Board of Adjustment) case # A-: N/A	Building Lot Coverage percentage N/A (site plans only)
CUD (Conditional Use District) case # Z-: N/A	

Stormwater Information	
Existing Impervious Surface 0.67 acres/square feet	Flood Hazard Area ■ Yes ☐ No
Proposed Impervious Surface 1.83 acres/square feet	If Yes, please provide
Neuse River Buffer ☐ Yes ☐ No Wetlands ☐ Yes ■ No	(Alluvial Soils) Flood Study FEMA Map Panel # 3720173600J

CONFORMITY WITH THE COMPREHENSIVE PLAN (Applicable to all developments)

Provide a description of how your plan conforms to the guidelines of the Comprehensive Plan 2030.

Zoned Residential with 10 D.U./Acre
Proposed Residential

FOR SUBDIVISION, APARTMENT, TOWNHOUSE, CONDOMINIUM PROJECTS ONLY

1. Total # Of Townhouse Lots Detached: N/A Attached N/A	11. Total number of all lots: 36
2. Total # Of Single Family Lots: 33	12. Is your project a cluster unit development? ☐ Yes ■ No
3. Total # Of Apartment Or Condominium Units: N/A	If Yes, please answer the questions below:
4. Total # Of Congregate Care Or Life Care Dwelling Units: N/A	a) Total number of Townhouse Lots
5. Total # Of Mobile Home Lots: N/A	b) Total number of Single Family Lots
6. Total Number of Hotel Units: N/A	c) Total number of Group Housing Units
7. Overall Total # Of Dwelling Units (1-6 Above): 33	d) Total number of Open Space Lots
8. Bedroom Units 1br 2br ■ 3br 4br or more	e) Minimum Lot Size
9. Overall Unit(s)/Acre Densities Per Zoning District(s) 10 D.U./Acre	f) Total Number of Phases
10. Total number of Open Space (only) lots: 1	g) Perimeter Protective Yard Provided ☐ Yes ☐ No
	h) Must provide open space quotient per City Code 10-3071 (5)

SIGNATURE BLOCK (Applicable to all developments)

In filing this plan as the property owner(s), I/we do hereby agree and firmly bind ourselves, my/our heirs, executors, administrators, successors and assigns jointly and severally to construct all improvements and make all dedications as shown on this proposed subdivision plan as approved by the City.

I hereby designate SEPI ENGINEERING & CONSTRUCTION to serve as my agent regarding this application, to receive and respond to administrative comments, to resubmit plans on my behalf and to represent me in any public meeting regarding this application.

I/we have read, acknowledge and affirm that this project is conforming to all application requirements applicable with the proposed development use.

Signed Waleed Elhady for Art Builders LLC Date 1/31/15

Signed Abdul Badawi for MYCC Date 1/31/15

Yattrib Qasis 1/31/15

TO BE COMPLETED BY APPLICANT	YES	N/A	TO BE COMPLETED BY CITY STAFF YES	NO	N/A
General Requirements					
1. Filing Fee for Plan Review – Payments may be made by cash, Visa, Master Card or check made payable to: City of Raleigh (No fee for Infill recombination)	x		✓		
2. **Preliminary Development Plan Application** completed and signed by the property owner	x		✓		
3. Client must complete and print page 1 and 2 of the **Preliminary Development Plan Application** to the plan cover sheet (not applicable for infill recombination)	x	☐	✓		
4. I have referenced the **Preliminary Development Plan Checklist** and by using this as a guide, it will ensure that I receive a complete and thorough first review by the City of Raleigh	x		✓		
5. Provide the following plan sheets:	x				
a) Cover sheet: includes general notes, owner's name, contact's name, telephone number, mailing address and email address	x		✓		
b) Existing Conditions Sheet	x	☐	✓		
c) Proposed Site or Subdivision Plan	x		✓		
d) Proposed Grading and Stormwater Plan	x	☐	✓		
e) Proposed Utility Plan, including Fire	x	☐	✓		
f) Proposed Tree Conservation Plan	x	☐	✓		
g) Proposed Landscaping Plan (Landscape Plan not required for commercial subdivisions)	x	☐	✓		
h) Building elevations that show maximum height from natural and finished grade, buildings to be removed	☐	x			✓
i) Transportation Plan Site	☐	x	✓		
6. Ten (10) sets of proposed plans to engineering scale (1" = 20', 1" =100', etc.), and date of preparation. For re-submittals only – include all revision dates	x		✓		
7. Plan size 18"x24" or 24"x36"	x		✓		
8. A vicinity map no smaller/less than 1"=500' and no larger than 1"=1000' to the inch, showing the position of the subdivision with its relation to surrounding streets and properties, and oriented in the same direction as the preliminary plan	x		✓		
9. Include sheet index and legend defining all symbols with true north arrow, with north being at the top of the map	x		✓		
10. Digital copy of only the plan and elevations. Label the CD with the plan name, case file number, and indicate how many times the plan has been resubmitted for review	x		✓		
11. Wake County School Form, if dwelling units are proposed	x	☐	✓		
12. Preliminary stormwater quantity and quality summary and calculations package	x	☐	✓		
13. For secondary tree conservation areas, include two (2) copies of the tree cover report completed by a certified arborist, North Carolina licensed landscape architect, or North Carolina registered forester Page 4101	☐	x			

LEGEND

- PROPERTY LINE (PL)
- R/W — RIGHT-OF-WAY LINE
- SETBACK LINE
- UTILITY EASEMENT
- STORM EASEMENT
- X — X — PROPOSED FENCE

GENERAL SITE NOTES

1. STREET TREES SHOWN IN LOCATIONS AS APPROXIMATE, SPACED AT AN AVERAGE OF 40 O/C. CONTRACTOR TO COORDINATE FINAL LOCATIONS WITH DRIVEWAY PLACEMENT AND OBTAIN APPROVAL FROM OWNER PRIOR TO INSTALLATION.
2. EXISTING UTILITIES ARE SHOWN FROM THE BEST AVAILABLE INFORMATION AND ARE APPROXIMATE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THESE AND OTHER UTILITIES BEFORE STARTING CONSTRUCTION. NOTIFY UTILITY LOCATING COMPANY (ONE CALL @ 1-800-632-4949) OR INDIVIDUAL UTILITY OWNERS FOR UNDERGROUND LOCATIONS AT LEAST 48 HOURS IN ADVANCE.
3. PROTECT ALL PROPERTY MONUMENTS AND PINS. MONUMENTS AND PINS THAT WILL BE DISTURBED DURING CONSTRUCTION SHALL BE REFERENCED AND REPLACED BY A LICENSED LAND SURVEYOR AT A COST TO THE CONTRACTOR.
4. IF DEPARTURES FROM THE DRAWINGS OR SPECIFICATIONS ARE DEEMED NECESSARY BY THE CONTRACTOR, DETAILS OF SUCH DEPARTURES AND REASONS THEREOF SHALL BE SUBMITTED IN WRITING TO THE OWNER FOR REVIEW. NO DEPARTURES FROM THE CONTRACT DOCUMENTS WILL BE ALLOWED WITHOUT APPROVAL BY THE OWNER.
5. NO SIGHT OBSTRUCTING, OR PARTIALLY OBSTRUCTING WALL, FENCE, FOLIAGE, BERM, SIGN, PARKED VEHICLE, OR OTHER OBJECT BETWEEN THE HEIGHTS OF TWO (2) FEET AND EIGHT (8) FEET ABOVE THE CURB LINE ELEVATION (OR THE EDGE OF PAVEMENT IF NO CURB EXISTS) SHALL BE PLACED WITHIN A SIGHT TRIANGLE.
6. MINIMUM CORNER CLEARANCE FROM CURB LINE OF INTERSECTION STREETS SHALL BE AT LEAST TWENTY (20) FEET FROM THE POINT OF TANGENCY.

MUSLIM YOUTH COMMUNITY CENTER
YATHRIB OASIS LLC
D.B. 15536, PG. 1462
PIN: 1736150379
ZONING: CUD R-10
AREA: 503458 SQ FT
11.56 ACRES

GRAPHIC SCALE
50 0 25 50 100
(IN FEET)
1 inch = 50 ft.

PRELIMINARY - DO NOT USE FOR CONSTRUCTION

Yathrib

811 3 WORKING DAYS BEFORE YOU DIG FOR THE LOCATION OF UNDERGROUND FACILITIES
Know what's below. Call before you dig.

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTICE:
CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR; NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK, OF PERSONS ENGAGED IN THE WORK, OF ANY NEARBY STRUCTURES, OR OF ANY OTHER PERSONS.

SEPI ENGINEERING & CONSTRUCTION
1025 WADE AVENUE
RALEIGH, NORTH CAROLINA
919.789.9977
5960 FAIRVIEW RD., SUITE 102
CHARLOTTE, NORTH CAROLINA
704.714.4880
330 SHIPYARD BLVD, SUITE 203
WILMINGTON, NORTH CAROLINA
910.523.5715
www.sepiengineering.com

SEPI ENGINEERING GROUP, INC. CORPORATE SEAL C-2197 N.C.

COPYRIGHT © 2014
SEPI ENGINEERING & CONSTRUCTION, INC

CAD FILE	REVISIONS	DATE

YATHRIB LLC REAL ESTATE INVESTMENTS

THE OASIS

PRELIMINARY SITE LAYOUT PLAN

5520 LOUISBURG ROAD
RALEIGH, NORTH CAROLINA 27616

PROJECT MANAGER	FIELD SURVEY DATE:
M. CRAIG	12/09/2013
CHECKED BY:	DRAWING DATE:
J. BEARD	02/06/2015
DRAWN BY:	JOB #:
B. MUELLER	SC14.002.00

SHEET
C-3.0


NIF RICORYAN LLC D.B. 15696 PG 1668 PIN: 1736153839 ZONING: IND-1
NIF YVONNE J NAJEM JOUMANA J NAJEM D.B. 15197 PG 155 PIN: 1736156869 ZONING: R-1
NIF VIOLA JACKSON RIDDICK PIN: 1736153719 ZONING: R-1
NIF PREGNANCY SUPPORT SERVICES OF WAKE FOREST NORTH CAROLINA D.B. 15598/ PG 1373 PIN: 1736156487 ZONING: R-6 CU
NIF JOHNNY B JEFFERYS ETHEL M JEFFERYS D.B. 1430 PG 150 PIN: 1736059934 ZONING: R-1
NIF JOHNNY B JEFFERYS ETHEL M JEFFERYS D.B. 2504 PG 721 PIN: 1736057866 ZONING: R-1
NIF JOHNNY B JEFFERYS ETHEL M JEFFERYS D.B. 1609 PG 145 PIN: 1736058886 ZONING: R-1
NIF MARVIN ONEAL RIDDICK D.B. 1439 PG 495 PIN: 1736151772 ZONING: R-1
NIF CYNTHIA D BROOKS AND CHRISTOPHER L HAYES ESTATE FILE: 14E-2465 PIN: 1736151636 ZONING: R-1
NIF JAMES LOUIS DUNN AND WIFE JOYCE D. DUNN D.B. 4763, PG. 603 PIN: 1736153833 ZONING: R-1
NIF JAMES LOUIS DUNN AND WIFE JOYCE DUNN D.B. 2166, PG. 98 PIN: 1736154519 ZONING: R-1
NIF JAMES LOUIS DUNN AND WIFE JOYCE D. DUNN D.B. 9344, PG. 2705 PIN: 1736154565 ZONING: R-1
NIF JAMES LOUIS DUNN AND WIFE JOYCE D. DUNN D.B. 9344, PG. 2713 PIN: 1736154427 ZONING: R-1
NIF MARTHA J JONES DAVID UTLEY D.B. 7722 PG 164 PIN: 1736058901 ZONING: R-1
NCDOT RIGHT-OF-WAY PER PROJECT #8.1402106
S82°05'02"E 459.00'
ROCK OUTCROP
15' x 10' CITY OF RALEIGH TRANSIT EASEMENT
36 59,570 SF, 1.37 AC MAX IMPERVIOUS _____ SF
50' SHOD-3 YARD
GRAVEL DRIVE
PAVED DRIVE
EXISTING 1 STORY BRICK HOUSE TO REMAIN
S64°04'32"W 286.89'
S20°53'52"E 271.53'
NIF JAMES ARTIS RIVERS AND KRISTEN MICHELLE RIVERS D.B. 11357, PG. 1681 PIN: 1736155309 ZONING: R-1
NIF JAMES ARTIS RIVERS AND KRISTEN MICHELLE RIVERS D.B. 10720, PG. 1001 PIN: 1736155312 ZONING: R-1
NIF VIOLA HUNTER JACKSON PIN: 1736155205 ZONING: R-1
35 108,906 SF, 2.50 AC MAX IMPERVIOUS _____ SF
MUSLIM YOUTH COMMUNITY CENTER YATHRIB OASIS LLC
D.B. 15536, PG. 1462
PIN: 1736150379
ZONING: CUD R-10
AREA: 503458 SQ FT
11.56 ACRES
PRIMARY TREE CONSERVATION AREA PERMANENTLY PROTECTED UNDISTURBED OPEN SPACE
NIF CLEMENTINE ROBERTSON JONES UTLEY, MARTHA JONES PIN: 1736055742 ZONING: R-1
NIF MICHAEL R UTLEY GLENDA B UTLEY D.B. 8206 PG 1696 PIN: 1736058671 ZONING: R-1
50' SHOD-3 YARD
N45° 55' 35"W 301.49'
STREET "A" 64' RIGHT-OF-WAY (NEIGHBORHOOD YIELD)
R = 500.00'
L = 64.69'
STREET "B" 50' RIGHT-OF-WAY (NEIGHBORHOOD STREET)
S45° 55' 35"E 54.39'
R = 350.50'
L = 45.34'
STREET "C" 50' RIGHT-OF-WAY (NEIGHBORHOOD STREET)
S38° 30' 59"E 247.92'
R = 524.50'
L = 116.60'
R = 43.00'
L = 75.69'
N38° 30' 59"W 247.92'
S20°53'52"E 220.48' TOTAL
N62°06'08"W 970.02' TOTAL
1 5632 SF
2 4545 SF
3 4545 SF
4 4545 SF
5 4545 SF
6 4545 SF
7 4545 SF
8 5427 SF
9 4365 SF
10 4383 SF
11 4490 SF
12 5340 SF
13 4853 SF
14 4434 SF
15 4434 SF
16 4434 SF
17 4434 SF
18 4835 SF
19 4785 SF
20 4915 SF
21 5733 SF
22 16222 SF
23 6584 SF
24 5930 SF
25 4802 SF
26 3746 SF
27 4052 SF
28 4052 SF
29 4052 SF
30 4052 SF
31 4052 SF
32 4369 SF
33 6653 SF
34 SHARED STORMWATER FACILITY 0.36 AC.
N24°08'41"E 117.46'
S01°10'12"W 418.20'
S64°08'41"W 586.45'
R/W MONUMENT
CL R/W MONUMENT
NIF BRANDEMERE HOMEOWNERS ASSOCIATION INC D.B. 15801 PG 2244 PIN: 1736053426 ZONING: R-1
NIF MARTHA J JONES DAVID UTLEY D.B. 7722 PG 164 PIN: 1736054468 ZONING: R-1
NIF MICHAEL R UTLEY GLENDA B UTLEY D.B. 8206 PG 1696 PIN: 1736055810 ZONING: R-1
NIF CLEMENTINE ROBERTSON D.B. 2259 PG 11 PIN: 1736051252 ZONING: R-1
NIF AMH 2014-3 BORROWER LLC D.B. 15854 PG 2374 PIN: 1736052268 ZONING: R-10 CU
NIF CARMEN L HURDLE D.B. 15897 PG 789 PIN: 1736053221 ZONING: R-10 CU
NIF WILLIE A JONES D.B. 1291, PG. 492 PIN: 1736055075 ZONING: R-1
NIF EVANS JONES HEIRS PIN: 1736056033 ZONING: R-1
NIF MAURICE JONES D.B. 1291 PG. 495 PIN: 1736049842 ZONING: R-1
NIF JANICE WALL ROBERTSON HEIRS ESTATE FILE: 13E 2948 PIN: 1736047911 ZONING: R-1
NIF FREDRICK JONES D.B. 1940, PG. 356 PIN: 1736047889 ZONING: R-1
NIF GLADYS J BURT HEIRS D.B. 1291, PG. 490 PIN: 1736048815 ZONING: R-1
NIF HELEN A. BURTON D.B. 1291, PG. 487 PIN: 1736048873 ZONING: R-1
NIF WINDSOR JONES PIN: 1736049729 ZONING: R-1
NIF RODNEY MIMS AND WIFE GLADYS MIMS D.B. 4276, PG. 654 PIN: 1736049766 ZONING: R-1
NIF RODNEY MIMS AND WIFE GLADYS MIMS D.B. 4276, PG. 652 PIN: 1736140712 ZONING: R-1
NIF LOUISE M GOODSON D.B. 2006, PG. 142 B.O.M. 1985, PG. 1626 B.O.M. 1948, PG. 65 PIN: 1736144690 ZONING: R-1
NIF VIOLA JACKSON D.B. 11048, PG. 374 PIN: 1736155112 ZONING: R-1
NIF CLYDE MARCELLUS RIDDICK AND WIFE CORA H RIDDICK D.B. 9344, PG. 2720 PIN: 1736145715 ZONING: R-1
EXISTING WOOD BARN
NIF CLYDE MARCELLUS RIDDICK AND WIFE CORA H RIDDICK D.B. 9344, PG. 2720 PIN: 1736145508 ZONING: R-1
PRIMARY TREE CONSERVATION AREA PERMANENTLY PROTECTED UNDISTURBED OPEN SPACE
NIF NC DEPARTMENT OF TRANSPORTATION D.B. 8085, PG. 131 PIN: 1736054038 ZONING: R-1
NIF ROOSEVELT JONES PIN: 1736054695
RAILROAD
RAILROAD RIGHTOF WAY
RAILROAD BUFFER
RAILROAD BUFFER
RAILROAD BUFFER

LEGEND

- PROPERTY LINE (PL)
- RW — RIGHT-OF-WAY LINE
- SETBACK LINE
- UTILITY EASEMENT
- 140 — EXISTING MAJOR CONTOUR
- 139 — EXISTING MINOR CONTOUR
- 140 — PROPOSED MAJOR CONTOUR
- 139 — PROPOSED MINOR CONTOUR
- SF — SF — PROPOSED SILT FENCE
- TP — TP — PROPOSED TREE PROTECTION FENCE
- LD — LD — PROPOSED LIMITS OF DISTURBANCE
- TEMPORARY DIVERSION DITCH
- PROPOSED STORM DRAINAGE PIPE
- SS — PROPOSED GRAVITY SEWER
- W — PROPOSED WATER LINE
- CHECK DAM
- INLET PROTECTION
- INLET PROTECTION FILTER
- HORSESHOE INLET PROTECTION FILTER
- SILT FENCE OUTLET
- CONSTRUCTION ENTRANCE
- FLARED END SECTION
- STORM MANHOLE
- YARD INLET
- CATCH BASIN
- FLOW ARROW

NITROGEN CALCULATIONS

Total Site

(1) Type of Land Cover	(2) Site Area (Acres)	(3) TN Export Coeff. (lbs/ac/yr)	(4) TN Export by Land Use (lbs/yr)	(5) TN Export From Site (lbs/ac/yr)
Residential Land Cover Areas - Method 1				
Area associated with new residential development	7.12		52.43	
Average for Residential				7.36
Residential Area	7.12 ac			

*** For buydown option eligibility, provide treatment to reduce the loading rate to 6 lbs/ac/year or less for residential development

Commercial Land Cover Areas - Method 2				
Area associated with new commercial development	4.44		59.44	
Average for Commercial				13.40
Commercial Area	4.44 ac			

*** For buydown option eligibility, provide treatment to reduce the loading rate to 10 lbs/ac/year or less for commercial development

Total Area	11.56 ac

Combined Nitrogen Goal for Buydown Option Eligibility 7.54

Adjusted Nitrogen Loading after Treatment

(1) Type of Land Cover	(2) Total Site Area (Acres)	(3) TN Export Coeff. (lbs/ac/yr)	(4) Total TN Export (lbs/yr)	(5) TN Export From Site (lbs/ac/yr)
Total Area associated with new development	11.56		65.26	
Average for Site				5.65

*** For buydown option eligibility, provide treatment to reduce the loading rate to the combined goal or less for the combined development

Buydown option used to further reduce TN loading to targeted rate of 3.6 lbs/ac/year:

GRADING NOTES

1. BOUNDARY & TOPOGRAPHIC INFORMATION TAKEN FROM A SURVEY ENTITLED "BOUNDARY SURVEY" PREPARED FOR: MYCC LLC. SITUATED IN THE NEUSE TOWNSHIP, WAKE COUNTY, NORTH CAROLINA PREPARED BY ANTHONY DIBONA OF BOUNDARY ZONE INC. DATED DECEMBER 9, 2013.
2. TOPOGRAPHICAL INFORMATION GATHERED UNDER THE SUPERVISION OF SEPI ENGINEERING & CONSTRUCTION, INC.
3. PROPOSED TOPOGRAPHY SHOWN HEREIN IS PRELIMINARY. REFER TO APPROVED INFRASTRUCTURE CONSTRUCTION PLANS FOR FINAL DESIGN TOPOGRAPHY
4. THE TREE PROTECTION FENCE SHALL BE MAINTAINED ON THE SITE UNTIL ALL SITE WORK IS COMPLETED AND THE FINAL SITE INSPECTION PRIOR TO THE CERTIFICATE OF OCCUPANCY (CO) IS SCHEDULED. THE FENCING SHALL BE REMOVED PRIOR TO FINAL SITE INSPECTION FOR THE FINAL INSPECTION.
5. THE TOP OF GRADE AND BOTTOM OF GRADE ELEVATIONS ARE GROUND ELEVATIONS AT THE RETAINING WALL. SEE RETAINING WALL DETAIL SHEET C-13.0.

GRAPHIC SCALE

50 0 25 50 100

(IN FEET)

1 inch = 50 ft.

PRELIMINARY - DO NOT USE FOR CONSTRUCTION

Yathrib

811 — 3 WORKING DAYS BEFORE YOU DIG FOR THE LOCATION OF UNDERGROUND FACILITIES

Know what's **below.** **Call** before you dig.

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTICE:

CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR; NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK, OF PERSONS ENGAGED IN THE WORK, OF ANY NEARBY STRUCTURES, OR OF ANY OTHER PERSONS.

SEPI ENGINEERING & CONSTRUCTION
1025 WADE AVENUE
RALEIGH, NORTH CAROLINA
919.789.9977
5960 FAIRVIEW RD., SUITE 102
CHARLOTTE, NORTH CAROLINA
704.714.4880
330 SHIPYARD BLVD, SUITE 203
WILMINGTON, NORTH CAROLINA
910.523.5715
www.sepiengineering.com

SEPI ENGINEERING GROUP, INC. CORPORATE SEAL C-2197 N.C.

COPYRIGHT © 2014 SEPI ENGINEERING & CONSTRUCTION, INC

CAD FILE

REVISIONS	DATE

YATHRIB LLC REAL ESTATE INVESTMENTS

THE OASIS

PRELIMINARY GRADING & DRAINAGE PLAN

5520 LOUISBURG ROAD
RALEIGH, NORTH CAROLINA 27616

PROJECT MANAGER: M. CRAIG	FIELD SURVEY DATE: 12/09/2013
CHECKED BY: J. BEARD	DRAWING DATE: 02/06/2015
DRAWN BY: B. MUELLER	JOB #: SC14.002.00

SHEET

C-5.0



LEGEND

- PROPERTY LINE (PL)
- R/W — RIGHT-OF-WAY LINE
- SETBACK LINE
- UTILITY EASEMENT
- SS — SS — PROPOSED GRAVITY SEWER
- W — W — PROPOSED WATER LINE
- PROPOSED STORM DRAINAGE PIPE
- G — G — PROPOSED GAS LINE
- OHE — OHE — PROPOSED OVERHEAD ELECTRIC LINE
- UGE — UGE — PROPOSED UNDERGROUND ELECTRIC LINE
- FO — FO — PROPOSED FIBER OPTIC LINE
- Ⓢ PROPOSED SS MANHOLE
- • PROPOSED SS CLEANOUT
- WM PROPOSED WATER METER
- ⊗ PROPOSED GATE VALVE
- PROPOSED FIRE HYDRANT ASSEMBLY

GENERAL UTILITY NOTES

1. EXISTING UTILITIES ARE SHOWN FROM THE BEST AVAILABLE INFORMATION AND ARE APPROXIMATE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THESE AND OTHER UTILITIES BEFORE STARTING CONSTRUCTION. NOTIFY UTILITY LOCATING COMPANY (ONE CALL @ 1-800-632-4949) OR INDIVIDUAL UTILITY OWNERS FOR UNDERGROUND LOCATIONS AT LEAST 48 HOURS IN ADVANCE.
2. ALL MATERIALS & CONSTRUCTION METHODS SHALL BE IN ACCORDANCE WITH CITY OF RALEIGH DESIGN STANDARDS, DETAILS & SPECIFICATIONS (REFERENCE: COR PUD HANDBOOK, CURRENT EDITION)
3. ANY NECESSARY FIELD REVISIONS ARE SUBJECT TO REVIEW & APPROVAL OF AN AMENDED PLAN &/OR PROFILE BY THE CITY OF RALEIGH PUBLIC UTILITIES DEPARTMENT PRIOR TO CONSTRUCTION
4. CONTRACTOR SHALL MAINTAIN CONTINUOUS WATER & SEWER SERVICE TO EXISTING RESIDENCES & BUSINESSES THROUGHOUT CONSTRUCTION OF PROJECT. ANY NECESSARY SERVICE INTERRUPTIONS SHALL BE PRECEDED BY A 24 HOUR ADVANCE NOTICE TO THE CITY OF RALEIGH PUBLIC UTILITIES DEPARTMENT
5. CONTACT THE UTILITY COMPANY TO RELOCATE ANY EXISTING UTILITY POLES. ALL EXISTING FACILITIES WHICH CONFLICT WITH THE IMPROVEMENTS UNDER THE SCOPE OF THIS PROJECT MUST BE RELOCATED AT THE EXPENSE OF THE APPLICANT.

GRAPHIC SCALE
50 0 25 50 100
(IN FEET)
1 inch = 50 ft.

PRELIMINARY - DO NOT USE FOR CONSTRUCTION

Yathrib

811 — 3 WORKING DAYS BEFORE YOU DIG FOR THE LOCATION OF UNDERGROUND FACILITIES
Know what's below. Call before you dig.

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTICE:
CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR; NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK, OF PERSONS ENGAGED IN THE WORK, OF ANY NEARBY STRUCTURES, OR OF ANY OTHER PERSONS.

SEPI ENGINEERING & CONSTRUCTION
1025 WADE AVENUE
RALEIGH, NORTH CAROLINA
919.789.9977
5960 FAIRVIEW RD., SUITE 102
CHARLOTTE, NORTH CAROLINA
704.714.4880
330 SHIPYARD BLVD, SUITE 203
WILMINGTON, NORTH CAROLINA
910.523.5715
www.sepiengineering.com

[redacted]

SEPI ENGINEERING GROUP, CORPORATE SEAL C-2197 N.C.

COPYRIGHT © 2014
SEPI ENGINEERING & CONSTRUCTION, INC

CAD FILE

REVISIONS	DATE

YATHRIB LLC REAL ESTATE INVESTMENTS

THE OASIS

PRELIMINARY UTILITY PLAN

5520 LOUISBURG ROAD
RALEIGH, NORTH CAROLINA 27616

PROJECT MANAGER	FIELD SURVEY DATE:
M. CRAIG	12/09/2013
CHECKED BY: J. BEARD	DRAWING DATE: 02/06/2015
DRAWN BY: B. MUELLER	JOB #: SC14.002.00

SHEET
C-6.0