



NOTES:

& S-5

1. The pavement cut shall be defined by a straight edge and cut with an approved sawcut machine.
2. The trench subgrade material shall be backfilled with suitable material and compacted to a density of at least 95% of that obtained by compacting a sample of the material in accordance with AASHTO T-99 as modified by NCDOT.
3. The final 1' of fill shall consist of ABC material compacted to a density equal to 100% of that obtained by compacting a sample of the material in accordance with AASHTO T-80 as modified by NCDOT.
4. The entire thickness and vertical edge of cut shall be tacked.
5. The same depth of pavement material which exists shall be reinstated, but in no case shall the asphalt be less than 2" thick.
6. The asphalt pavement material shall be installed and compacted thoroughly with a smooth drum roller to achieve a smooth level patch.
7. Refer to City of Raleigh standards for trenches and pipe bedding (S-4 & S-5) for additional details.
8. No hand patching allowed.
9. Pavement cuts within NCDOT ROW shall conform to the approved on site encroachment permit.

CITY OF RALEIGH				
DEPARTMENT OF PUBLIC UTILITIES				
STANDARD ASPHALT				
PAVEMENT PATCH DETAIL				
DWG. NO.	REVISIONS	DATE	REVISIONS	DATE
S-3	D.W.C.	11-1-99	A.B.B.	4-19-04
	RRH	3-30-00		